

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONSERVATION COMMISSION
5-7-1959
MAY 7 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 32-39 County: Rooks

Location: CSE SE Sec. 14 Twp. 10 Rge. 20 (E) (W)

Name of Field: Total Depth: 3789

I have this date completed supervision of plugging of:

Lease Name: Sutor Well No. 8

Operator's Full Name: I. O. Miller

Complete Address: Box 274 Ellis, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? Reason:

Operation Completed: Hour 5PM Day 25 Month 4 Year 59

The above well was plugged as follows:

8 5/8" at 227' circulated with cement @ 5 1/2" 3783' with 100 sax cement.
Filled with sand to 3770', set 4 sax cement with dump bsl er, pulled
2995' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" (38 sax Cel)
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 150', displaced
20 sax cement through 5 1/2" at 150', heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edson Pette*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 14 T 10 R 20
BOOK PAGE 32 LINE 39