

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-15-1969
DEC 15 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name I. O. Miller

Complete Address 619 Brown Bldg., Wichita, Kansas 67202

Lease Name Miller-Sutor Well No. 9

Location NW SW SE Sec. 14 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3786'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling, Co.

Address Box 221 Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11A Day 12 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 3786' 8 5/8 csg set at 220' cwc 185 sk.

5 1/2 csg set at 3782' cw 100 sk cmt.

5 1/2 csg perf. (3644-3648) Dakato Squeezed.

Filled 5 1/2 csg W/sd (3600-3786) Dumped 5 sk cmt W/dump bailer. (3560-3600)

Cutoff and recovered 800' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls, plug and 100 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/15/69
INV. NO. 1037-W