

*Handwritten mark*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
3-2-1970  
MAR 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Sutor "B" Well No. 1

Location SE NW NE Sec. 25 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3767

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 4:15P Day 27 Month 2 Year 1970

The above well was plugged as follows:

RTD 3767' 8 5/8 csg set at 224' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo F. Massey*  
Well Plugging Supervisor

INVOICED

DATE 3/2/70

INV. NO. 1526-W