


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 25-3

LOCATION SW SW NW

SEC. 25 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Earl

Operator Morganstern & Specter Address Box 661 Russell, Kans

Field _____ County Rooks

Total Depth 3707 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1670' circulated with cement 575 sax - 5 1/2" 3700' with 100 sax cement behind.

Filled with sand to 3690', set 4 sax cement with dump bailer 1/2 pulled 3020' 5 1/2" - circulated hole with heavy mud through 5 1/2" - 25 sax gel - pumped cementing plug through 5 1/2" at 550', followed by 35 sax cement - heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Edon Kelly
District Conservation Agent

Date 7-11-57

RECEIVED
STATE CORPORATION COMMISSION
7-13-1957

PLUGGING
FILE SEC. 25 T. 10 R. 20 W
BOOK PAGE 25 LINE 3

CONSERVATION DIVISION
WICHITA, KANSAS