

KANSAS

49
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-22-1968
OCT 22 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name Sutor "L" Well No. 1

Location SW NE NE Sec. 25 Twp. 10 Rge. 20 (E) (W) X

County Rooks Total Depth 3769

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 9:30P Day 20 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3769' 8 5/8 csg set at 247' cwc Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/22/68
INV. NO. 8678-4

Signed: Bio J. Messer
Well Plugging Supervisor