

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-28-1962
MAY 28 1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks
Location: SW SE SW Sec. 28 Twp. 10 Rge. _____ (E) _____ (W) 20
Name of Field: _____ Total Depth: 3729

I have this date completed supervision of plugging of:
Lease Name: Tribble Well No. 2

Operator's Full Name: Sterling Drg Co

Complete Address: Box 127 Sterling, Kansas

Plugging Contractor Knight Casing Pulling Co

Address: Chase, Kans License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 23 Month 5 Year 62

The above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/2" 3721' with 100 sax cement.
Sand to 3700', set 4 sax cement with dump bailer, pulled 1485' 5 1/2" to
550'- circulated hole with heavy mud through 5 1/2" at 550' (18 sax Gel),
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled
to bottom cellar with cement.

Mudding and cementing by Knight Company Pump Truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 6/4/62
INV. NO. 5084-W