

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 47 9

LOCATION SU SW NE

SEC. 25 TWP. 10 RGE. 20

Dry Hole ^X Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1-C Lease Sutor

Operator Birmingham-Bartlett Address 300 West Main St.,
Wichita, Kans

Field County Rooks

Total Depth 3738 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 173' circulated with cement - 5 1/2" at 3732' with
160 sax cement behind.

Filled with mud to 3725' set 4 sax cement with dump bailer,
pulled 3000' 5 1/2", filled hole with mud to 170', set rock
bridge to 160' and 15 sax cement, filled with mud to 35',
set rock bridge and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
12-18-1950
DEC 18 1950
CONSERVATION DIVISION
Edson
District Conservation Agent

PLUGGING
FILE SEC 25 T 10 R 20
BOOK PAGE 47 LINE 9

Date 12-13-50