

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 144-30
LOCATION C S 1/2 SE NE
SEC. 25 TWP. 10 RGE. 20 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Sutor _____

Operator Bennett & Roberts Address Russell, Kans

Field _____ County Rooks

Total Depth 3779 Feet.

Plugging Contractor Earl Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 246' circulated with cement - 5 1/2" at 3777' with 75 sax
cement behind.

Filled with sand to 3760', set ~~4~~ 4 sax cement with dump bailer.

pulled 3100' 5 1/2" - filled hole with heavy mud to 245', set rock and
20 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

Earl Miller
District Conservation Agent
Date 3-8-57
3-12-1957
DIVISION
KANSAS

PLUGGING
FILE SEC. 25 T. 10 R. 20 W
BOOK PAGE 144 LINE 30