

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,597-00-00

LEASE NAME Trellis

WELL NUMBER #1

SPOT LOCATION SE NE NE

SEC. 12 TWP. 12 RGE. 21 (E) or (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 10-7-85

Plugging Completed 10-17-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Strata Energy Resources Corp.

ADDRESS 413 W. 14th, Hays, Kansas 67601

PHONE # (918-625-6118) OPERATORS LICENSE NO. 7875

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	261'	None
				4-1/2"	4048'	1,058.31'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3870' and 4 sacks cement. Shot casing at 3300', 3000' and 2500'. Pulled 26 joints of 4-1/2" casing. Squeezed well with 3 sacks gel, 4 sacks hulls 30 sacks cement, 17 sacks gel, 1/2 sack hulls, 70 sacks cement, 10 sacks gel, 1/2 sack hulls, released plug and pumped 70 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111


Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1985



RECEIVED
STATE CORPORATION COMMISSION
Notary Public
Iona M. Leatherman
10-21-1985
OCT 21 1985

My Commission expires: