

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-196-22127-00-00 ¹⁹⁵

LEASE NAME Zachman

WELL NUMBER #1

3960' Ft. from S-Section Line

330' Ft. from E Section Line

SEC. 18 TWP. 12S RGE. 21W (E) or (W)

COUNTY Trego

Date Well Completed 9/12/93

Plugging Commenced 9/12/93

Plugging Completed 9/12/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ESP Development, Inc.

ADDRESS R.R. 1, Box 18, Paradise, KS 67658

PHONE# (913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 9/12/93 (date)

by Hays, Kansas (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>Wichita, Kansas</u>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Plugged with 200 sacks 60/40 poz., 6% gel and 1/4# flo seal per sack.

1st plug @ 1778' with 25 sacks. 2nd plug @ 940' with 100 sacks.

3rd plug @ 275' with 40 sacks. Wiper plug @ 40' with 10 sacks to surface. 10 sacks in mousehole and 15 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ESP Development, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

Bud Eulert

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Bud Eulert

(Address) RR 1 Box 18 Paradise KS 67658

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1993

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1993

CONSERVATION DIVISION
Wichita, Kansas

DOMINA SUPER
State of Kansas
My Appt. Exp. 2-9-97

Donna Super
Notary Public

My Commission Expires: 2-9-97

DRILLERS WELL LOG

API# 15-195-22127-00-00

DATE COMMENCED: September 5, 1993
DATE COMPLETED: September 12, 1993

ESP Development, Inc.
ZACHMAN #1
C E/2 E/2 NE
Sec. 18-12S-21W
Trego County, Kansas

ELEVATION: 2293' G.L.
2298' K.B.

0 - 240'	Sand, Shale
240 - 420'	Shale
420 - 1155'	Sand, Shale
1155 - 1743'	Sand, Shale, Red bed
1743 - 1785'	Anhydrite
1785 - 1850'	Shale
1850 - 2291'	Shale, Lime
2291 - 2390'	Shale
2390 - 2750'	Lime, Shale
2750 - 3284'	Shale
3284 - 3360'	Lime
3360 - 3625'	Shale, Lime
3625 - 3692'	Shale
3692 - 3935'	Shale, Lime
3935 - 4012'	Shale
4012'	R.T.D.

FORMATION DATA

Anhydrite	1743'
Base Anhydrite	1785'
Topeka	3345'
Heebner	3565'
L.K.C.	3599'
Base K.C.	3838'
Pawnee	3913'
Conglomerate	3976'
Arbuckle	None
R.T.D.	4012'

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1993

CONSERVATION DIVISION
Wichita, Kansas

Surface Pipe: Set Used 19#
8 5/8" casing at 235' with
160 sacks 60/40 poz., 2% gel,
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF RUSSELL) ss

Roy Vonfeldt of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Roy Vonfeldt
Roy Vonfeldt

Subscribed and sworn to before me this 17 day of Sept., 1993.

My Comm. Expires:

Aug. 5, 1994

Debbie Maier
Debbie Maier, Notary Public

