

15-163-03435-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 3-18-55

LEASE NAME Tribble

WELL NUMBER 3

1650 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 28 TWP. 10 RGE. 20 ~~10~~ (W)

COUNTY Rooks

Date Well Completed 3-18-55

Plugging Commenced 4-9-85

Plugging Completed 4-9-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Monsanto Oil Company

ADDRESS 3030 N.W. Expressway, Oklahoma City, Oklahoma 73112

PHONE# (405) 947-2361 OPERATORS LICENSE NO. 5457

Character of Well imput

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle & Lansing-Depth to Top 3369 Bottom 3768 T.D. 3768

Kansas City

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-Kansas City	Oil 3369-3629					
Arbuckle	Oil 3656-3768	Surface	200	8 5/8	200	None
		Surface	3756	5 1/2	3756	None
		Surface	?	4 1/2	?	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 4 1/2" casing 25 sx 60/40 poz 8% gel +25 sx 60/40 poz 8% gel w/hulls + 15 sx gel dropped plug and pumped down 75 sx 60/40 poz 8% gel at 1000#, shut down-400#. Pumped 25 sx 60/40 poz 8% gel down 4 1/2 x 5 1/2 annulus at 1000# shut down-400#. Pumped 75 sx 60/40 poz 8% gel down 5 1/2" x 8 5/8" annulus at 250# - shut down - 100#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B J - Titan License No. _____

Address Hays, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.

James P. Siebenthal (Employee of Operator) Wichita, Kansas of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James P. Siebenthal

(Address) 3030 NW Expressway, Okla. City, OK 73112

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 85

Julie Johnson
Notary Public

My Commission Expires: 12-23-87

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1985
5-3-1985

CONSERVATION DIVISION
Wichita, Kansas

State Corporation Commission
Conservation Division
(Oil, Gas and Water)

Time	Month	Day	Year

Called In

Elev. 2172 Anh. 1630

API 3-18-55

Dear Sir:

Mr. Robert J. Slaby of Monsanto Oil Company KCC/# 5457

Operator's Full Name Monsanto Oil Company KCC/# 5457

Complete Address: 3030 NW Expressway, suite 1203, Oklahoma City, Oklahoma 73112

Lease Name Trible Well # 3

Location SE NW SW Sec. 28 Twp 10 Rge 20 /W

County Rooks Total Depth 3768

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

8 5/8" 200 S.P. cwc w/ 125 sk. Cmt., 4 1/2" or 5 1/2" Csg. set @ 3756 ft.

w/ 100 sk. Cmt. Other size Csg. 4 1/2 from surface to unknown depth.

D. V. or squeezed @ 867, 1016, 921, 1168 ft. w/ 620 sk Cmt. No Did cement circulate?

Open Hole 3768 ft. Plug Back T.D. 3320 ft. Perf's 3369'; 3386'; 3439-41'; 3591'; 3613'; 3629'.
STATE CORPORATION COMMISSION
2-14-1985
FEB 14 1985

Static fluid after Csg. recovered _____ CONSERVATION DIVISION Kansas Shot _____ Recovered _____ Ft.

Any important information in regard to: S.P. - Csg. - Dakota - Fresh Water - other.

Plug production formations @

Operator's plugging recommendation: Spot or Squeeze - Amount of Cement and Gel. etc.

Time	Month	Day	Year

Cemented by _____

MJS:lr