

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,653

LEASE NAME Sutor 'A'

WELL NUMBER 2

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 25 TWP. 10 RGE. 20 ~~XX~~ or (W)

COUNTY Rooks

Date Well Completed 10-28-76

Plugging Commenced 8-26-92

Plugging Completed 8-26-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ANDERSON ENERGY, INC.

ADDRESS 200 E. First St., Suite 414

PHONE# (316) 265-7929 OPERATORS LICENSE NO. 6484

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 28, 1992 (date)

by Dave Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Arbuckle LKC. Depth to Top 3221 Bottom 3768 T.D. 3768

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka	Oil & Water	3221	77	8-5/8"	247'	0
LKC	Oil & Water	3442	3739	5-1/2"	3761'	0
Arbuckle	Oil & Water	3761	3765			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 2 shots @ 1610' and 930'. Ran 2" tubing to 2200' and pumped 200 sx. Pull tbg. and pump 50 sx down backside. Max. pressure 300# SIP 150# Pump 40 sx down casing. Blew hole in casing and topped w/10 sx. Slurry: 65-35 Poz, 10% gel, 500# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. _____

Address P. O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anderson Energy, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK

William L. Anderson (Employee of Anderson Energy, Inc. or operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William L. Anderson

(Address) 200 E. First St., Suite 414
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 28th day of September, 1992

Wilma E. Clark
Wilma E. Clark, Notary Public



Commission Expires: August 5, 1996