

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rocks \_\_\_\_\_ County. Sec. 28 Twp. 10S Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines 330' Sof NL & 1320' W of E1 SW 1/4

Lease Owner I. O. Miller

Lease Name Thomas Well No. 2

Office Address 619 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 27, 1955 19

Application for plugging filed December 27, 1955 19

Application for plugging approved December 27, 1955 19

Plugging commenced December 27, 1955 19

Plugging completed December 27, 1955 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	238	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

238 feet of 8 5/8" surface pipe circulated with cement

Circulated hole with heavy mud, set cementing plug at 220

feet, 1/2 sack hulls and 15 sacks of cement. Mudded hole

to 40 feet, set cementing plug, 1/2 sacks hulls and 10

sacks of cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Virginia Drilling Company, Inc.,  
Address 701 Brown Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
F. G. Treutle (employee of owner) or ~~owner or operator~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
619 Brown Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3<sup>rd</sup> day of January, 19 56

My commission expires January 31, 1957 Notary Public.

PLUGGING  
FILE NO. 28 T 10 R 20W  
BOOK 27 LINE 37

1-3-1956

Well: Thomas #2 330' S of North Line & 1320' W of East Line SW/4  
 Company: I. O. Miller Sec. 28-10-20, Rooks Co., Ks.  
 Contractor: Virginia Drilling Co., Inc.  
 Commenced: December 15, 1955  
 Completed: December 27, 1955  
 Rotary Depth: 3800  
 Elevation: 2169 D.F.

FORMATION	DEPTH	
Surface clay-shale-shells	0-280	8-5/8" csg. set @ 238
Shale	200-220	
Sand	220-230	
Shale-shells	230-650	TOPS:
Shale-sand	650-820	Heebner 3436
Shale-shells	820-1090	Toronto 3457
Sand	1090-1250	K. C. Lansing 3473
Shale-shells	1250-1630	Base K.C. 3697
Anhydrite	1630-1675	Conglomerate 3723
Shale-shells	1675-2180	
Shale-lime	2180-2205	
Broken lime	2205-2350	
Lime	2350-2575	
Shale-lime	2575-3065	
Lime	3065-3160	
Lime-shale	3160-3265	
Lime	3265-3785	
Conglomerate	3785-3800	

*S. A. Murphy*  
 S. A. Murphy

Subscribed and sworn to before me, a Notary Public, this 28<sup>th</sup> day of December, 1955.

*Inez M. Underwood*  
 Notary Public-Inez M. Underwood

My commission expires: March 15, 1958.

PLUGGING  
 SEC 28 T10 R 20W  
 PAGE 27 LINE 37

1-3-1956