


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 28 Twp. 10 Rge. 20 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW SE SW
Lease Owner Sterling Drilling Company
Lease Name Tribble Well No. 2
Office Address Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 4-21-62 19
Application for plugging approved 5-10-62 19
Plugging commenced 5-22-62 19
Plugging completed 5-23-62 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty.
Producing formation Depth to top Bottom Total Depth of Well 3729 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				5-1/2"	3721'	1477'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3729', sanded to 3700' and dumped 4 sacks of cement @ 3700' with dump bailer. Pulled 5 1/2" casing to 950', ~~circulated~~ circulated with gel mud and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 370' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed mud to 35' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

6-4-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (SUPERVISOR) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 1962

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- TRIBLE #2

Location: SW SE SW, Section 28-10-20W, Rooks County, Kansas

OWNER: Sterling Drilling Company, et al.
ROTARY DRILLING CONTRACTOR: Group Exploration Company
CABLE TOOL CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-10-55 (w.r.)
2-28-55 (w.c.t.)
COMPLETED: 2-21-55 (w.r.)
3-5-55 (w.c.t.)

ROTARY TOTAL DEPTH: 3729'

RECEIVED
STATE CORPORATION COMMISSION
5-10-1962
MAY 10 1962

CONSERVATION DIVISION
Wichita, Kansas

Log

0 - 70 Soil & Sand
70 - 600 Shale & Shells
600 - 1400 Shale & Sand
1400 - 1600 Shale
1600 - 1650 Limestone
1650 - 1900 Shale
1900 - 2425 Shale & Limestone
2425 - 2850 Limestone
2850 - 3190 Shale & Limestone
3190 - 3615 Limestone
3615 - 3665 Limestone & Shale
3665 - 3710 Limestone
3710 - 3720 Shale
3720 - 3729 Arbuckle Limestone T.D.

CASING RECORD

Ran 200' of 8 5/8" casing with
125 sacks bulk cement and 1
sack calcium chloride.

Set 5 1/2" casing at 3721 with
100 sacks bulk cement.

CABLE TOOLS M.I.C.T. Swabbed mud and drilled cement. Swab tested at rate of 8 bbls. of oil per hour. Acidized with 500 gal., maximum pressure 550#. Tested at rate of 10 bbls. of oil per hr. M.O.C.T.