


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 25 Twp. 10 Rge. 20 (E) (W)
Location as "NE/CNW&SW" or footage from lines SW/SW/NW
Lease Owner Morgenstern & Spector NW AND YCC
Lease Name Earl Well No. #2
Office Address Russell Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 7-9 19 57
Plugging completed _____ 7-17 19 57
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3726' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,033'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 3726'.
Plugging started 7-9-57. Finished 7-17-57.
Plugged off bottom with sand to 3705' and dumped 5 sacks cement with bailer. Shot 5 1/2" casing at 3,033'. Pumped mud and circulated. Pulled pipe to 550' and pumped cement. Layed down rest of pipe. Plugged well with mud to 35'. Set rock bridge and dumped 10 sacks cement for cap on well. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1957.

My commission expires November 8, 1960. Betty S. Edman Notary Public.

PLUGGING
FILE SEC 25 T 10 R 20W
BOOK PAGE 25 LINE 4

7-31-1957

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock

Wichita, Kansas

15-163-04099-00-00


Company - GULF OIL CORPORATION
 Farm - Earl No. 2

SEC. 25 T. 10
 SW NW NW

Total Depth. 3726
 Comm. 4-2-50 Comp. 4-25-50
 Shot or Treated. 500 gals. acid
 Contractor.
 Issued. 7-8-50

County. Rooks

KANSAS



Elevation.

Production. Pot. 466 BOP

CASING:

8 5/8" 1583 cem. w/575 sx Left in
 5 1/2" 3716 cem. w/100 sx " "

Figures Indicate Bottom of Formations.

shale & shells	1550
shale	1580
Anhydrite	1615
shale & shells	2290
lime & shale	2380
lime	2500
lime & shale	3035
lime	3295
lime & shale	3430
lime	3625
chert & lime	3680
lime & shale	3713
lime, RTD	3720
lime	3726
Total depth	
Tops:	
Heebner	3370
Lansing	3408
Conglomerate	3652
Simpson	3696
Arbuckle	3715

From top cellar on 5 1/2" casing to rotary bushing is 5'.

Potential based on 8 hour state physical test.

7-2-1957

PLUGG
 EC. 25 T. 10 20w
 BOOK PAGE 25 Ltr. 4