


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 25 Twp. 10 Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines: NW NW SW
Lease Owner Tennessee Gas Transmission Co.
Lease Name Imogene Ouder Kirk #1 Well No. _____
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 5-1 1950
Application for plugging filed 1-7 1958
Application for plugging approved 1-9 1958
Plugging commenced 1-7-58 19____
Plugging completed 1-10-58 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Pettty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3715 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1553'	none
				5-1/2"	3702'	2537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole and found it open.
Filled w/sand to 3690' and ran 4 sacks
of cement. Pulled 5 1/2" casing to 600'
and pumped in 13 sacks of mud and 20
sacks of cement. Pulled to 440' and
pumped in 20 sacks of cement. Pulled
rest of pipe, cleared hole, mudded the
hole to 35', set a rock bridge and ran
10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
1-18-1958
JAN 18 1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Glen E. Armour (employee of owner) of STATE OF KANSAS of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour
(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1958

My commission expires 9-27-58

Thomas V. Gagner
Notary Public.

PLUGGING
FILE NO. 25 T 10 R 204
BOOK 74 LINE 40

CORPORATION COMMISSION

OF KANSAS

WELL RECORD

PRODUCER: Midstates Oil Corporation
 ADDRESS: 518 National Bank of Tulsa Building, Tulsa 3, Oklahoma
 FARM NAME: Ouderkirk WELL NUMBER: One
 WELL LOCATED: 0 Km/Corner NE 1/4 SW 1/4 Section 25-10E-20N, Nowata County, Kansas
 POTENTIAL TEST: Taken July 10, 1950 - 33 barrels in 24 hours
 COMMENCED DRILLING: March 23, 1950 DRILLING COMPLETED: April 6, 1950
 ACIDIZED WITH: 1000 gallons of acid ELEVATION: 2124'

CASING RECORD

<u>Size</u>	<u>Where Landed</u>	<u>No. Sacks Count</u>
6-5/8"	1553'	800 sacks
5-1/2"	3702'	200 sacks

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>
Shale	0	215
Sand and shale	215	465
Shale and shells	465	675
Shale and sand	675	1090
Sand and shale	1090	1230
Shale and shells	1230	1350
Red bed and shale	1350	1590
Anhydrite	1590	1561
Remaining	0	1554
Anhydrite	1561	1595
Red bed and shale	1595	1599
Salt and shale	1599	2215
Shale, and lime	2215	2635
Lime, shale	2635	3230
Lime	3230	3525
Lime and shale	3525	3630
Lime and shale	3630	3703
Core #1 - shale	3703	3708
Core #2 - shale	3708	3715
Total Depth		3715

Producing From: Arbuckle Lime

Signed: Geo. M. Vandaveer, Jr.
 Geo. M. Vandaveer, Jr.
 Vice-President

DATE: September 19, 1950

RECEIVED
 CORPORATION COMMISSION
 1-8-1958
 JAN 8 1958

PLUGGING
 FILE SEC 25 T. 12 R. 226
 BOOK PAGE 74 LINE 40