


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 25 Twp. 10 Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. SE NW SW
Lease Owner Tennessee Gas Transmission Co.
Lease Name Imogene Ouder Kirk #2 Well No. _____
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 5=27 _____ 19.50
Application for plugging filed _____ 1-7 _____ 19.58
Application for plugging approved _____ 1-9 _____ 19.58
Plugging commenced _____ 1-11-58 _____ 19.
Plugging completed _____ 1-16-58 _____ 19.
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19._____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3691 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1528'	none
				5-1/2"	3674'	2554'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Check the hole to 2503', found fluid.
Bailed off fluid and push plug to 3299'.
Ran sand and 4 sacks of cement. Pulled
5 1/2" casing to 600' and pumped in 30 sacks
of mud and 20 sacks of cement. Pulled
casing to 400' and pumped in 20 sacks of
cement. Pulled all of 5 1/2" casing. ~~REMOVED~~
Ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 22 1958
1-22-1958
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Glen E. Armour (employee of owner) ~~XXXXXXXXXXXXXXXXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 58

Thomas V. Higgins
Notary Public.

My commission expires 9-27-58

PLUGGING
FILED 8-25-10 120W
BOOK 100-74 1-41

CORPORATION COMMISSION
OF KANSAS
WELL RECORD

PRODUCER: Midstates Oil Corporation
 ADDRESS: 518 National Bank of Tulsa Building, Tulsa 3, Oklahoma
 FARM NAME: Onderkirk WELL NO.: Two
 WELL LOCATED: E SE NW SW of Section 25-102-20W, Becks County, Kansas
 POTENTIAL TEST: Taken June 20, 1950 - 317 barrels in 24 hours.
 COMMENCED DRILLING: May 9, 1950 DRILLING COMPLETED: May 27, 1950
 ACIDIZED WITH: 1000 gallons of acid

CASING RECORD

<u>Size</u>	<u>Where Landed</u>	<u>No. Sacks count</u>
8-5/8"	1574'	750 sacks
5-1/2"	3674'	700 sacks

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Shale & sand	0	730
Sand	730	850
Sand, shale	850	1100
Sand	1100	1240
Shale, red bed	1240	1572
Anhydrite	1572	1565
Red bed	1565	1850
Shale	1850	1950
Shale, shells	1950	2167
Shale, lime	2167	2790
Lime, shale	2790	3395
Lime	3395	3496
Lime, shale	3496	3527
Lime	3527	3580
Lime, shale	3580	3667
Shale	3667	3675
Arbuckle	3675	3680
Correction in measurement	3680	3682
Lime, Arbuckle	3682	3684
Arbuckle	3684	3691
Total Depth		3691

RECEIVED
JAN 8-1956
CONCRETE DIVISION

Signed: Geo. M. Vandaveer, Jr.
 Geo. M. Vandaveer, Jr.
 Vice-President

Date: June 26, 1950

DRILLING
 NO. 25110 R 200
 BOOK PAGE 74 LINE 41

u. Lowe