


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 25 Twp. 10 Rge. 20 (W) SW/SW/NW
Location as "NE/CNW/SW" or footage from lines
Lease Owner Morgenstern and Spector
Lease Name Earl Well No. #1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 7-6 1957
Plugging completed _____ 7-11 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3707' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,068'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 3707'.
Plugging started 7-6-57. Finished 7-11-57.
Plugged off bottom with sand to 3690' and dumped 5 sacks cement with bailer.
Shot 5 1/2" casing at 3,068'. Pumped 25 sacks mud and circulated. Pulled pipe to 550'. Pumped 35 sacks cement and layed down rest of pipe. Plugged well as follows: Mud to 35'. Set rock bridge and dumped 10 sacks cement for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 1957.
Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

RECEIVED
STATE CORPORATION COMMISSION
7-16-1957
JUL 16 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25T 10 R 20W
BOOK PAGE 25 LINE 3


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - Gulf Oil Corp.
Farm - Earl No. 1

SEC. 25 T. 10 R. 20W
SW SW NW

Total Depth. 3707
Comm. 2-25-50 Comp. 3-16-50
Shot or Treated. Acidized w/1000 gals
Contractor.
Issued. 4-29-50

County. Rooks
KANSAS



CASING:
8 5/8" 1670 cem w/575 sx
5 1/2" 3700 cem w/100 sx

Elevation. _____

Production. 400 Bbls 8 hr phy.
pot.

Figures Indicate Bottom of Formations.

sand	90
clay, shale	290
shale, shells	475
sand, shale	1330
shale, shells	1545
red bed, shale	1573
anhydrite	1600
shale, shells	2175
lime, shale	2495
lime	2771
shale, lime	3135
lime	3355
lime, shale	3678
lime	3701
deepened with cable tools to: lime	3707
Total Depth	

Tops:

Heebner	3353
Toronto	3373
Lansing	3390
Base K. C.	3620
Pennsylvanian basal conglomerate	3642
Simpson	3675
Arbuckle	3694

STATE RECEIPT
7-2-1957

COMMISSIONER OF GEOL. & MINES
WICHITA, KANSAS

PLUGGING		
SEC.	25	T. 10 R. 20W
PAGE	25	LINE 3