


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Rooks \_\_\_\_\_ County. Sec. 25 Twp. 10 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
NE NE SE  
Lease Owner Southern States Oil Co.  
Lease Name Trarbach Well No. 1  
Office Address Box 1365, Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Dry Hole  
Date Well completed December 29, 1976  
Application for plugging filed Dec. 29 1976  
Application for plugging approved Dec. 29 1976  
Plugging commenced Dec. 29 1976  
Plugging completed Dec. 29 1976  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole full of heavy mud.  
Bottom plug at 720' w/70 sks. 50/50 pozmix, 6% Gel thru drill pipe  
Middle plug at 240' with 20 sacks " " " " " "  
Top at 40',  $\frac{1}{2}$  sk. hulls, plug and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

1-3-1977  
JAN 03 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Box 823 Great Bend, KS.

STATE OF Kansas COUNTY OF Barton, ss.  
Larry Curtis (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
Box 823 - Great Bend, Ks. 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of December, 19 76

My commission expires April 11, 1978  
Clorady M. Hague Notary Public.

Drillers' Well Log

Date Commenced: December 18, 1976  
 Date Completed: December 29, 1976

Southern States Oil Co.  
 TRARBACH #1  
 NE NE SE  
 Sec. 25, Twp. 10, Rge 20W  
 Rooks County, Ks.

0 - 630' Shale  
 630 - 770' Red Bed  
 770 - 940' Sand  
 940 - 1599' Red Bed  
 1599 - 1642' Anhydrite  
 1642 - 3414' Shale & Lime  
 3414 - 3419' Heebner Shale  
 3419 - 3437' Shale & Lime  
 3437 - 3451' Lime & Shale  
 3451 - 3681' Lime  
 3681 - 3762' Lime & Shale  
 3762 - 3785' Dolomite

Elevation: 2201 K.B.

## Formation Data

Anhydrite	1599
Heebner	3414
Toronto	3437
Lansing	3451
Base K.C.	3681
Arbuckle	3762
RTD	3785

Surface Pipe: Set used 28#  
 pipe at 280' with 160 sacks cement,  
 2 $\frac{1}{2}$  Gal, 3 $\frac{1}{2}$  cc.

## A F F I D A V I T

State of Kansas  
 County of Barton ) ss.

Larry Curtis of lawful age does swear and state that the facts and Statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 30 day of December 1976.

My Comm. Expires:  
April 11, 1978

Donna M. Zague  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 1-3-1977  
 JAN 03 1977  
 CONSERVATION DIVISION  
 Wichita, Kansas