

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 28 Twp. 10S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Leben & Bankoff

Lease Name Romine Well No. 1

Office Address Box 486, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-9-66 19

Application for plugging filed 3-9-66 19

Application for plugging approved 3-9-66 19


Plugging commenced 3-9-66 19

Plugging completed 3-9-66 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3804 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	182'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Plug @ 540' with 20 sacks cement
Set Plug @ 180' with 20 sacks cement
Bridged Plug @ 40' with 1/2 sack hulls and 10 sacks cement

3-14-1966
M.F.N. 76
1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF ~~KANSAS~~ KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 66

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Leben & Bankoff
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: ROMINE #1
 LOCATION: NW NE NE Sec. 28-10S-20W
 ROOKS COUNTY, KANSAS
 COMMENCED: 3-1-66
 COMPLETED: 3-9-66

0	40	Clay, Sand
40	60	Post Rock
60	830	Shale
830	1115	Sand, Shale
1115	1360	Shale, Sand
1360	1635	Redbed
1635	1680	Anhydrite
1680	2145	Shale, Shells
2145	2887	Lime, Shale
2887	3055	Shale, Lime
3055	3385	Lime, Shale
3385	3628	Lime
3628	3700	Lime, Shale
3700	3757	Lime
3757	3782	Lime, Shale
3782	3804	Arbuckle
	<u>3804</u>	<u>RTD - D. & A.</u>

NOTARY PUBLIC
 STATE OF KANSAS
 3-14-1966
 MAR 14 1966
 COURT REPORTERS & DRUGS
 WILSON, KANSAS

Set 8 5/8" new surface casing @ 182' with 150 sacks Common 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Romine #1 well, located NW NE NE of Section 28, Township 10 South, Range 20 West, Rooks County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 11th day of March, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967