

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rocks _____ County. Sec. 25 Twp. 10 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner Tennessee Gas Transmission Co.
Lease Name Imogene Ouderkirk #6 Well No. _____
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 1-7 _____ 19____ 58
Application for plugging approved _____ 1-9 _____ 19____ 58
Plugging commenced 1-16-58 _____ 19____
Plugging completed 1-18-58 _____ 19____
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3700' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	191'	none
				7"	3695'	607'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3700' and found it open. Filled w/sand to 3690' and ran 4 sacks of cement. Pulled 1 jt 7" and pumped in 28 sacks of mud and 20 sacks of cement. Pulled 9 jts 7" and pumped in 20 sacks of cement. Pulled rest of 7" (5 jts), bailed to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
-23-1958
JAN 23 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Glen E. Armour (employee of owner) of ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of January, 1958

Thomas V. Hugin
Notary Public.

My commission expires 9-27-58

PLUGGING
FILE SEC. 25 T. 10 R. 20
BOOK PAGE 74 LINE 43

CORPORATION COMMISSION

OF KANSAS

WELL RECORD

PRODUCER: Midstates Oil Corporation

ADDRESS: 518 National Bank of Tulsa Bldg., Tulsa 3, Oklahoma

FARM NAME: Ouderkirk WELL NO. Six

WELL LOCATED: NW NE SW Section 25-10S-20W, Rooks County, Kansas

DRILLING COMMENCED: December 13, 1950 DRILLING COMPLETED: December 27, 1950

POTENTIAL TEST: Taken January 16, 1951 - produced 190 barrels in 24 hours on pump.

ACIDIZED WITH: 250 gallons of acid GRAVITY OF OIL: 23° API

PRODUCING FORMATION: Arbuckle Lime 3694 to 3700'.

CASING RECORD

<u>Size</u>	<u>Where Landed</u>	<u>No. Sacks Cement</u>
10-3/4"	191'	125 sacks
7"	3695'	200 sacks

<u>Formation</u>	<u>Top</u>	<u>Bottom</u>
Sand, shale - reaming	0	191
Shale, shells	191	300
Shale	300	1000
Sand	1000	1115
Red bed, shale, shells	1115	1555
Anhydrite	1555	1590
Red bed, shale, shells	1590	1805
Shale, salt	1805	2050
Shale, lime	2050	2161
Lime, shale	2165	2329
Shale	2329	2461
Lime, shale	2461	2834
Shale	2834	2990
Lime, shale	2990	3552
Lime	3552	3577
Lime & shale	3577	3629
Conglomerate	3629	3672
Simpson	3672	3685
Shale	3685	3697
Core #1 - Arbuckle Lime	3697	3699
Core #2 - Arbuckle Lime	3699	3703
Correction in measurement	3703	3700
Total Depth		3700

Signed: Geo. M. Vandaveer, Jr.
Vice President

Date: February 16, 1951

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
H.L. SEC 25 T 10 R 20W
BOOK PAGE 74 LINE 42