


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 25 Twp. 10 Rge. 20W (E) (W)
Location as "NE/CNW%SW%" or footage from lines CS/2 SE NE
Lease Owner Bennett & Roberts Oil Operations
Lease Name Sutor Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12/23 19 56
Application for plugging filed 2/28 19 57
Application for plugging approved 3/1 19 57
Plugging commenced 3/2 19 57
Plugging completed 3/7 19 57
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3779 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	246'	None
				5 1/2"	3777 1/2'	3117

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 3760', dumped 4 sax cement @ 3760' with dump bailer. Top of cement 3725'. Filled hole with mud to 240', set rock bridge, dumped 20 sax cement. Top of cement, 190'. Filled hole with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of March, 19 57

My commission expires 6/17/58

Alara Hummel Notary Public.
STATE CORPORATION COMMISSION
3-15-1957
MAR 15 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25 T. 10. R. 20W
BOOK PAGE 144 LI. E. 30

Bennett & Roberts Oil Operations
Sutor #1

CR/2 SE NE Sec. 25-10-20
Rooks County, Kansas

Contractor: Bennett & Roberts Drilling, Inc.

Casing Record

M.T.D. 3776
Cable Tool T.D. 3779
Commenced 12/2/56
Completed 12/13/56

8 5/8" Set @ 246' w/150 sx cnt.
5 1/2" Set @ 3776 1/2 w/75 sx cnt.

Post Rock	15
Sand	55
Sand & Shale	80
Gray shale	220
Blue Shale Hard	240
Blue Shale	260
Shale, Gyp.	714
Red Bed & Gray Shale	865
Sand	925
Red Rock	950
Red Bed & Shells	1135
Sand	1180
Shale & Red Bed	1620
Anhydrite	1680
Shale & Shells	2120
Lime & Shale	3340
Lime	3480
Lime & Chert	3813
Lime	3740
Chert, Lime & Shale	3770
Conglomerate	3779
Correction TD	3778
Conglomerate	3779

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Luwin

Subscribed and sworn to before me this 21st day of December, 1956.

Blara Hummel
Notary Public

My Commission Expires 6/17/58

NOTARY PUBLIC
COMMISSION
12-1-1957
Wichita, Kansas

PLUGGING
FILE SEC 25 T 10 R 20W
BOOK PAGE 144 LINE 30