

15-163-03406-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 27 Twp 10 Rge. 20 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-NW-NW-SE
Lease Owner Sunray Oil Corporation
Lease Name Ponge Pongue Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 9/25 1951
Application for plugging filed 9/27 1951
Application for plugging approved 9/28 1951
Plugging commenced 9/25 1951
Plugging completed 9/25 1951
Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	Dry	3394	3485	8 5/8"	246	None
Conglomerate	Dry	3639	3735			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 250' and set plug. Dumped 15 sack cement on plug. Mudded hole to 40' and set second plug. Filled hole with cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
W.E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.
Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10th day of October, 1951.

Martha Scott
Notary Public.

My commission expires April 19, 1952

23-3273-s 4-50-10M

PLUGGING
FILE SEC 27 T 10 R 20
BOOK PAGE 11 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1951

C. C. mm.

15-163-03406-0000

WELL RECORD

Sturmy Oil Corporation
H. O. Poague #1.
Drilling Com. 9-8-51 Rotary
Drilling Comp. 9-25-51 Rotary
Drilling Contractor, H. M. Williams

NW/4 NW/4 SE/4
Sec. 27-10S-20W
Rocks County, Kansas.
Casing
8 5/8" 246'

FIGURES INDICATE BOTTOM OF FORMATIONS.

Production: Dry

Sand and shale	135
Shale & Lime	255
Shale	620
Shale & Shells	1845
Shale	2015
Salt, Shale & Lime	2205
Lime, Shale & Red Rock	2320
Lime, Broken	2390
Shale & Lime	2510
Lime	2730
Shale	2795
Blue Shale	2840
Shale & Shells	2880
Shale	2990
Shale & Shells	3060
Lime & Shale	3135
Shale & Shells	3186
Lime & Shale	3330
Lime	3358
Lime & Shale	3385
Lime	3530 (Drill Stem Test at 3485)
Lime & Shale	3555
Lime	3620
Lime & Shale	3687
Lime	3697
Lime & Shale	3735
Total Depth	3735

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, W. E. Westbrook, Jr., do hereby certify that the above is a true and correct log of the above described well.

W. E. Westbrook, Jr.

Subscribed and sworn to before me this 29th day of September, 1951.

Walter Scott
Notary Public

My commission expires: 4-19-52

PLUGGING
FILE SEC-27-T-10-R-200
BOOK PAGE 11 LINE 31