

15-163-03259-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 27 Twp. 10 Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C N/2 NE SW

Lease Owner The Derby Oil Company

Lease Name Towns Well No. 1

Office Address Box 1030, 420 W. Douglass, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 12, 1952

Application for plugging filed June 12, 1952

Application for plugging approved June 12, 1952

Plugging commenced June 12, 1952

Plugging completed June 12, 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3757 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	258'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 3757' to 241 $\frac{1}{2}$ ' - Heavy Rotary Mud
- 241 $\frac{1}{2}$ ' to 240' - Wooden Plug
- 240' to 41 $\frac{1}{2}$ ' - $\frac{1}{2}$ Sack Hulls & 15 Sacks Cement & Rotary Mud
- 41 $\frac{1}{2}$ ' to 40' - Wooden Plug
- 40' to Surface - $\frac{1}{2}$ Sack Hulls & 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Champlin Refining Company

Address Enid, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

F. W. Heiser (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Assistant-to-the-President
Box 1030, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of June, 1952

My commission expires August 24, 1953

Notary Public.

23-8390-s 6-51-20M




THE DERBY OIL COMPANY

WELL RECORD

PRODUCTION DEPARTMENT

15-163-03259-0000

640 Acres
N



Locate well correctly

LEASE Towns WELL NO. 1

RECORD COMPILED June 19, 1952 BY Bob Douglass

SEC. 27 TWP. 10 RGE. 20W COUNTY Rooks STATE Ka.

LOCATION N/2 NE SW ACRES 160

STAKED BY Don Bowman DATE 19

ELEVATION GROUND 2127 D. F.: 2132 K. B.: 2135

ALL MEASUREMENTS ARE FROM Kelly Bushing

TOOLS	STARTED	COMPLETED	FROM	TO	CONTRACTOR
ROTARY	6/1/52	6/12/52	0	3757	Champlin Refining Co.
CABLE	None				

PRODUCTION DATA Dry & Abandoned

CASING AND TUBING RECORD

SIZE HOLE DRILLED	DEPTH	CASING SIZE	WT.	THDS.	MAKE, TYPE, GRADE, NEW, USED	CASING POINT	PULLED	LEFT IN	CEMENT		REMARKS
									SACKS	ESTIMATED TOP	
12 1/2 IN.	258'	8 5/8"	2 1/4#		J-55 - new	258'		258'	150	Surface	

WELL LOG

FORMATION	FROM	TO	NO. OF FEET	DRLG. TIME	FORMATION	FROM	TO	NO. OF FEET	DRLG. TIME
Surface sand & shale	0	258	258		Lime & shale	3398	3414	16	
Shale & shells	258	1074	816		Lime & chert	3414	3454	40	
Shale, sand & redbed	1074	1605	531		Lime	3454	3560	106	
Shale & shells	1605	1615	10		Lime & shale	3560	3618	58	
Anhydrite	1615	1655	40		Shale & lime	3618	3655	37	
Shale, shells, redbed	1655	1860	205		Chert, shale, & lime stringers	3655	3746	91	
Shale, salt, shells	1860	2172	312		Dolomite	3746	3757	11	
Shale & shells	2172	2295	123		R.T.D.	3757			
Shale & lime	2295	2435	140						
Shale & lime	2435	2525	90						
Lime & shale	2525	2695	170						
Shale	2695	2770	75						
Shale & lime	2770	2885	115						
Lime & shale	2885	2990	105						
Shale & lime	2990	3215	225						
Lime & shale	3215	3286	75						
Lime	3286	3378	92						
Black shale	3378	3381	3						
Shale & lime	3381	3398	17						

RECEIVED
STATE CORPORATION
JUN 27 1952
CONSTRUCTION
Wichita, Kansas
PLUGGING
FILE 258-27-10-R-20
BOOK PAGE 25 LINE 1

