

15-163-03101-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 27 Twp. 10S Rge. 20 (E) W (W)

Location as "NE/CNW&SWK" or footage from lines C NW NE NW

Lease Owner The Derby Oil Company

Lease Name Williams Well No. 4

Office Address P.O. Box 1030, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed Oct. 8 1954

Application for plugging filed Oct. 8 1954

Application for plugging approved Oct. 8 1954

Plugging commenced Oct. 8 1954

Plugging completed Oct. 8 1954

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	190'	8 5/8"	190'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3740' to 181 1/2' - heavy rotary mud  
 181 1/2' to 180' - wooden plug  
 180' to 134' - 15 sacks cement & 1/2 sack hulls  
 134' to 41 1/2' - heavy rotary mud  
 41 1/2' to 40' - wooden plug  
 40' to 6' - 10 sacks cement & 1/2 sack hulls  
 6' to surface - cellar

11-02-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLENN W. PEEL

Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
Glenn W. Peel (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL

(Signature) BY: *Glenn W. Peel*

P.O. Box 359, Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of October, 1954

My commission expires June 4, 1955

*Marian M. Hebert* Notary Public.



