


15-163-00098-0000

WELL PLUGGING RECORD

STATE COMMISSION
Give All Information Completely
Make Required Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rooks County Sec 29 Twp 10 Rge (E) 20 (W) X
Location as 'NE/CNW 1/4 SW 1/4' or footage from lines SW SW SW X
Lease Owner Doley Oil Company
Lease Name Thomas Well No 1
Office Address P.O. Box 473 Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole X
Date well completed 11/11/48 19 X
Application for plugging filed 4/5/49 19 X
Application for plugging approved 4/5/49 19 X
Plugging commenced April 5, 1949 19
Plugging completed April 12, 1949 19
Reason for abandonment of well or producing formation dry hole X
If a producing well is abandoned, date of last production 19 X
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty
Producing formation Depth to top Bottom Total Depth of Well 3671 Feet X
Show depth and thickness of all water, oil and gas formations. 3724 RTKLL

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 5 1/2 inch, 3248'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole to 3700'. Run 5 sacks of cement.
Mudded hole to 225'. Run 10 sacks of cement.
Mudded hole to 139'. Run 10 sacks of cement. Well Completed.
Mudded hole to 30 ft filled to bottom of cellar with cement.

RECEIVED

Conservation Division
MAY 6 - 1949

STATE CORPORATION COMMISSION KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Doley Oil Company
Address P.O. Box 473 Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
Ernest J. Doley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest J. Doley
Hays, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5 day of May 1949

Gabriel F. Ruppert Notary Public

My commission expires June 30, 1949

PLUGGING
FILE SEC 29 T 10 R 20
BOOK PAGE 21 LINE 23

Well: Thomas #1  
 Location: SW/cor. Section 29-10S-20W, Rooks County, Kansas  
 Company: Doley Oil Company  
 Contractor: Virginia Drilling Company, Inc.  
 Commenced: October 15, 1948  
 Completed: October 29, 1948  
 Total Depth: 3724 - R.T.D.  
 Elevation: 2123

FORMATION	DEPTH
Clay-shale	0-90
Shale-shells	90-142
Cement	130-141
Shale	141-380
Shale-iron	380-655
Shale	655-705
Sand	705-795
Shale	795-900
Sand-shale	900-1090
Sand	1090-1290
Shale	1290-1590
Anhydrite	1590-1650
Shale-shells	1650-1735
Shale-redbed	1735-1825
Shale-shells	1825-1955
Shale	1955-2075
Shale-sand	2075-2160
Shale-broken line	2160-2265
Shale-sand	2265-2387
Ft. Riley Lime & Shale	2387-2470
Shale-lime	2470-2485
Shale- (sticky)	2485-2530
Shale-lime-sand	2530-2631
Shale-lime	2631-2720
Shale-shells	2720-2843
Shale	2843-2890
Shale-lime	2890-2960
Shale	2960-3008
Shale-lime	3008-3455
Lime	3455-3530
Lime-shale	3530-3595
Lime	3595-3680
Chert	3680-3693
Lime-shale	3693-3717
Lime	3717-3724

Set 8-5/8" csg. @ 141  
 Set 5 1/2" @ 3719  
 Circ. @ 3510  
 3694 - 30 min.  
 3703 - 1 hr. 10 min.  
 3710 - 1 hr. 30 min.

TOPS:

Topeka	3164
Heebner	3362
Kansas City	3400
Arbuckle	3719

Now comes S. A. Murphy, who state that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Thomas No. 1, located in the SW/corner of Section 29-10S-20W, Rooks County, Kansas, was drilled to a total depth rotary of 3724 feet. Same was plugged and abandoned.

Subscribed and sworn to before me this 31<sup>st</sup> day of December, 1948.  
*S. A. Murphy*  
 \_\_\_\_\_  
*W. H. ...*  
 \_\_\_\_\_  
 Notary Public

My commission expires February 5, 1949

