

15-163-12373-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 29 Twp. 10 Rge. 20W (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW

Lease Owner Sunray Mid-Continent Oil Company

Lease Name Thomas Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 19 19 52

Application for plugging filed March 21 19 58

Application for plugging approved March 24 19 58

Plugging commenced October 9 19 58

Plugging completed October 12 19 58

Reason for abandonment of well or producing formation

Reached economic limit

If a producing well is abandoned, date of last production December 12 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3691 Bottom 3691 Total Depth of Well 3691 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	243	none
				5 1/2 OD	3683	1023

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3670' with sand and dumped 4 sacks of cement.
Pulled pipe to 500', circulated 10 sacks of mud and 20 sacks of cement. Pulled pipe up to 200', dumped 20 sacks of cement.
Set 10' rock bridge at 40'. Dumped 10 sacks of cement.

Well log attached.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E & L Casing Pulling Company
Address 1416 Coolidge, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
N. E. Montgomery (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *N. E. Montgomery*
Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October

My commission expires December 24, 1960

PLUGGING
FILE SEC. 29 T. 10 R. 20W
BOOK PAGE 89 LINE 45

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1960
Notary Public
CONSERVATION DIVISION
Wichita, Kansas

10-21-58

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
December 30, 1952

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: December 7, 1952
Drilling Completed: December 19, 1952

A.E. Thomas #1 SW-NW-
NW-Section 29-108-20W,
Rooks County, Kansas.

DRILLERS LOG

Surface Clay & Post Rock	0-100
Shale & Shells	100-1093
Sand Dakota	1093-1278
Red Bed	1278-1486
Red Bed - Shale	1486-1595
Anhydrite	1595-1630
Shale	1630-1686
Shale & Shells	1686-2100
Shale & Lime	2100-2305
Lime & Shale	2305-2385
Shale & Lime	2385-2835
Shale & Shells	2835-2889
Shale & Lime	2889-3190
Lime & Shale	3190-3357
Heebner Shale	3357-3360
Toronto	3360-3365
Lime & Shale	3365-3395
Lime	3395-3599
Lime - Shale	3599-3650
Conglomerate Simpson Shale Arbuckle	3650-3686 TD

I, Lillian T. Bonham, hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's A. E. Thomas #1 SW-NW-NW-Section 29-108-20W, Rooks County, Kansas.

Lillian T. Bonham
Lillian T. Bonham, Secy.

Edward Seckel
Notary Public

June 26 1953
My Commission Expires

PLUGGING	
FILE	SEC. 29 T. 10 R. 20W
BOOK	PAGE 89 LINE 45

RECEIVED
OCT 21 1958
CONSERVATOR DIVISION
WICHITA, KANSAS
OIL CORPORATION COMMISSION