

4- 060330

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,653
150' NW of
SE NW NE /4 SEC. 25, 10 S, 20 W
4396 feet from S section line
1756 feet from E section line

Operator license# 6484

Lease Sutor well # 2

Operator: Anderson Energy, Inc.

County Rooks

122.26

Address: 200 E. 1st.
Suite 414
Wichita, Kansas 67202

Well total depth 3762 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: 11:00A.M Day: 26 Month: August Year: 92

Plugging proposal received from: Steve Robben

Company: Express Well Service Phone: 913-735-9405

Were: Order 350 sxs. 65/35 posmix - 10% gel.
Run tubing to plug.
Perforate anhydrite at 1610' and Base of Dakota at 930'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00P.M., Day: 26, Month: August, Year: 92

Actual plugging report: 8 5/8" to 247'. 5 1/2" to 3761'. Run tubing.
Pumped 200 sxs. cement and pulled tubing. Tied onto annulus and pumped
50 sxs. cement. Max. 300#. S.I.P. 50#. Tied onto production casing and
pump 50 sxs. cement. Blew out casing on top of braden head. Topped
well off with cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
8-31-1992
AUG 31 1992

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2186 GL

I did[] / did not[] observe the plugging.

[Signature]

(agent)
Form CP-2/3

INVOICED
DATE 9-24-92
INV. NO. 36246

[Signature]