

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-167-21,830-0000

SW, Sec. 27, T 10 S, R 20 WE

2310 feet from N/S section line

2310 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931

Lease Name Towns Well # 1

Operator: Bowman Oil Co.
Name &
Address P.O. Box 17
Codell, Mo. 67630

County Rooks

Well Total Depth 3760 feet

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8" feet 260'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pioneers Drilling Co., Inc. License Number 256

Address 308 W. Mill, Plainville, Mo. 67663

Company to plug at: Hour: 3:00 PM Day: 24 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Tom Aom

(company name) Pioneers Drilling Co., Inc. (phone) 913-434-4687

were: Order 200 sacks 50 posmix - 6% gel - 3% l.l. & 8 5/8" plug.
Spot w/ drill stem w/ heavy mud between all plugs. 1st plug @ 3755' w/
20 sacks, 2nd plug @ 1625' w/ 20 sacks, 3rd plug @ 850' w/ 100 sacks,
4th plug @ 300' w/ 40 sacks, 5th plug - solid bridge of shells & plug @ 40' w/
10 sacks. Circulate 10 sacks in rat hole.

Signed G. L. Schulz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 PM Day: 24 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 260' sp. cas. w/ 165 sacks 50 posmix - 2% gel - 3% l.l.

Ordered 200 sacks 50 posmix - 6% gel - 3% l.l. & 8 5/8" plug. Spot w/ drill
stem w/ heavy mud between all plugs. 1st plug @ 3755' w/ 20 sacks,
2nd plug @ 1625' w/ 20 sacks, 3rd plug @ 850' w/ 100 sacks, 4th plug @ 300'
w/ 40 sacks, 5th plug - solid bridge of shells & plug @ 40' w/ 10 sacks.
Circulated 10 sacks in rat hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed G. L. Schulz
(TECHNICIAN)

INVOICED
DATE 12-6-82
INV. NO. 1775-W