

6-18-87

To: 6 070568
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,927-0000

SE SW SW , SEC. 29 , T 10 S, R 20 (W)

330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Lease Name Whisman Well # 4

Operator: Black Diamond Oil Inc.
Name & Address: 1105 E. 30th # A
Hays, Kansas 67601

County Rooks 101.24

Well Total Depth 3115 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated Tag # 1808

Plugging Contractor Emphasis Oil Operations License Number # 8241

Address Box 56 Russell, Kansas

Company to plug at: Hour: 9:45 AM Day: 18 Month: June Year: 19 87

Plugging proposal received from Bill Owen

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: 8 5/8" - 227 ft. S.P. cuc With 150 sk 60/40 pozmix, 2% gel-3% Ca. CL by Allied Cement.

Proposal - 215 sk 60/40 pozmix 6% gel - 3% c. cl. - 1 sk flo cele, and 8 5/8" plug

Spot with drill stem, recondition hole, heavy mud between all plugs

Arbuckle at 3600 ft., Elev. 2135, Anhy 1564, Mud Cond. 9.4 weight,

Vis 42, water loss 8 to 12, 25 sk at 3600' - 25 sk at 1590' - 100 sk at 870'

40 sk at 270' - 10 sk at 40' - 15 sk in rat (circulate)

Plugging Proposal Received by *M. J. Schmidt* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 AM Day: 18 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Ordered 215 sk 60/40 pozmix 6% gel, 3 % ca.cl. 1 sk flo cele and

8 5/8" plug spotted with drill stem, reconditioned hole, heavy mud between plugs

1st plug at 3600 ' with 25 sk cmt, 2nd plug at 1590' with 25 sk cmt.

3rd plug at 870 ft. with 100 sk cmt and 1 sk flo cele - 4th plug at 270 ft with 40 sk cmt.

5th plug hulls and plug at 40 ft. w/10 sk cmt., 15 sk in rat hole (circulate)

Cemented by Allied Cementing

Remarks: 6-25-87

(If additional description is necessary, use BACK of this form.)

INVOICED (If not) observe this plugging.

Signed *Marion J. Schmidt* (TECHNICIAN)
Marion J. Schmidt

DATE 7-10-87

INV. NO. 17463