

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-21455-00-00

SW, Sec. 28, T 12 S, R 21 W/4

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6037

Lease Name Rigway Well # 1

Operator: Staab Oil Co.
Name & Address Box 39
Hwy 5 Ks 67601

County Trego

Well Total Depth 3935 feet 127.89

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 228

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Helberg Oil Co. License Number 5669

Address Box 32 Morland Ks.

Company to plug at: Hour: 2 AM Day: 6 Month: 3 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jerry Helberg

(company name) Helberg Oil Co. (phone) 913 627-4481

were: order 185 sx cem. 50/50 por mix 670 gal 390 c.c.

1 sx. hulls 1. 8 5/8 plug 1 sx Flow Seal.

Heavy mud between all plugs.

Pump Cem. down drill pipe.

Elev. 2242 Anhydrite 1649-98 Arbuckle No.

Dakota. 1650
592 = 900

Signed Dale Batthayor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ (None)

Operations Completed: Hour: 9: AM Day: 6 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1660 for 15 min.

25 sx @ 1660

100 sx @ 900 mixed with 1 sx. Flow Seal.

40 sx @ 280 1 sx hulls pushed plug to 40'

10 sx @ 40

10 sx in Rat hole

Remarks: _____

Cementing to Sun.

RECEIVED
STATE CORPORATION COMMISSION
03-12-1984
MAR 12 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Dale Batthayor
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICE
DATE 3-14-84
NO. 0752