

6 031053

3-15-88

193

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,990-0000  
NW SW SE SEC. 3212 <sup>JP-1ECC</sup>, T 10 S, R 20 W/E  
990 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name McKenna Well # 4

Operator: Helmerich and Payne Inc.

County                      Rooks 125.06

Name & Address P. O. Box 558

Well Total Depth 3848 feet

Garden City, Ks. 67846

Conductor Pipe: Size                      feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well                      Gas Well                      Input Well                      SWD Well                      D&A X

Other well as hereinafter indicated                     

Plugging Contractor R and C Drilling License Number                     

Address Hays, Kansas

Company to plug at: Hour: AM Day: 15 Month: Mar Year: 19 88

Plugging proposal received from John Wise

(company name) R and C Drilling (phone)                     

were: 8 5/8" set at 264' w/150 sks cwc. Circulate hole w/no less than 36 vis.

mud w/no loss or gain in fluid. Spot cement plugs w/drill pipe.

Balance plugs w/mud. Order 190 sks 60/40 Poz 6% Gel 3% C C. Halliburton

Cement Co. Pond Water.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All                      Part                      None X

Operations Completed: Hour: 12:15AM Day: 15 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs at 1625' w/25 sks

850' w/100 sks 1 sk Hulls

300' w/40 sks

40' w/10 sks W.P.

Cir 15 sks in rat hole w/joint of pipe

Plug complete.

Remarks: Elev. 2142' KB Anhy 1605' - 43'  
(If additional description is necessary, use BACK of this form.)

~~XXXX~~ **INVOICED** (did not) observe this plugging.

DATE 4-26-88

INV. NO. 20456

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow