

3-25-88

316

6 070655

API NUMBER 15-163-02216-0000 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C E/2 SE NW, SEC. 32, T 10 S, R 20 W/E

3300 feet from S section line  
2970 feet from E section line  
ANB kcc

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Schneider Well # 2

Operator: Coastal Oil and Gas Corp  
Name &

County Rooks 122.69

Address 211 N. Robinson #1700 OkC, Ok.  
Oklahoma City, Ok. 73102

Well Total Depth 3775 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address 1707 East 10th Street Hays, Ks. 67601

Company to plug at: Hour: 9:30AM Day: 25 Month: March Year: 19 88

Plugging proposal received from DonDeHerra

(company name) Coastal Oil and Gas Corp (phone) \_\_\_\_\_

were: 8 5/8" - 232' S.P. cwc w/125 sks cement. 5 1/2" casing set at 3775'  
w/100 sks cement. 5 1/2" casing squeezed at 1327' w/80 sks cement and 982' w/70 sks  
cement. No casing recovery. Proposal: Order 250 sks 65/35 Pozmix 10% Gel and  
5 sks Hulls. Perferate at 1560' and 852' with pump truck load and pressure with  
cement both 5 1/2" casing and annulus space.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:15AM Day: 25 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Ordered 250 sks Thrifty Mix 65/35 Pozmix 10% Gel

and 5 sks Hulls. Pumped in with pump truck. Pumped in 5 1/2" casing 25 sks cement  
followed with another 150 sks cement w/5 sks Hulls added in. Max pressure 600 Psig.  
shut in at 200 Psig. Pumped 35 sks in annulus max pressure 700 Psig. Shut in at  
500 Psig. Pumped remainder 40 sks cement in 5 1/2" casing. Max pressure 900 Psig.  
Shut in 600 Psig. Perferated on Commission and 1560'. By B.J. Titan

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: 06-01-88  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-21-88

INV. NO. 20900

observe this plugging.  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Marion J. Schmidt  
(TECHNICIAN)  
Marion J. Schmidt