

REC'D 3-25-88

317

6 070656

API NUMBER 15-163-02217-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NW, SEC. 32, T 10 S, R 20
3630 feet from S section line
3630 feet from E section line
ANB KCC

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Schneider Well # 3

Operator: Coastal Oil and Gas Corp

County Rooks 121.23

Name & Address 211 N. Robinson #1700

Well Total Depth 3730 feet

Oklahoma City, Ok 73102

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 235

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address 1707 East 10th Street Hays, Ks. 67601

Company to plug at: Hour: 11:30AM Day: 25 Month: March Year: 19 88

Plugging proposal received from Don DeHerra

(company name) Coastal Oil and Gas Corp (phone)
were: 8 5/8" - 235' S.P. cwc w/150 sks. 5 1/2" casing set at 3691' w/100 sks cement.

Perferated at 3691' to 3730'. Squeezed casing at 2778' w/200 sks cement.

No casing recovery. Proposal: perferate at 850' and 1555'. Order 250 sks Thrifty Mix 65/35 Pozmix 10% Gel and 5 sks Hulls. Pump in with pump truck, load and pressure annulus space and also 5 1/2" casing. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00PM Day: 25 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Ordered 250 sks 65/35 Poz 10% Gel and 5 sks Hulls. Pumped in with pump truck. Pumped in 5 1/2" casing 25 sks cement followed with another 175 sks cement with 5 sks Hulls added in. Max pressure 1000 Psig. Shut in at 600 Psig.

Pumped 50 sks in annulus. Max pressure 800 Psig. 600 Psig shut in. Perferated at 850' and 1555'.

Remarks: Cemented by B. J. Titan (If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

DATE 6-21-88

Signed Marion J. Schmidt (TECHNICIAN)

INV. NO. 20901