

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02222-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 32-10S-20W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: WAITX Well Number: 5
County: ROOKS RTFCC Total Vertical Depth: 3753 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

Conductor Pipe: Size feet: 8 1/2 1.97
Surface Casing: Size 8.625 feet: 156 100 SX CMT
Production: Size 5.5 feet: 3741 150 SX CMT
Liner: Size feet:

Well Type: EOB UIC Docket No: E24984.1 Date/Time to Plug: 11/21/2002 10:00 AM
Plug Co. License No.: 6568 Plug Co. Name: KAISER-FRANCIS OIL COMPANY
Proposal Rcvd. from: JOHN GLENN Company: KAISER-FRANCIS OIL COMPANY Phone: (620) 564-3214

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 200# hulls.
Arb. O.H. 3741' - 3753'.
Squeeze records: 01-1959 - 1200' w/167 sxs cement.
Re-squeezed: - 04-1959 - no cement amounts; 06-1970 - squeezed 935' and 1061' with 150 sxs cement.
04-1998 - ran 3 1/2" 9.2 #J-55 tubing - cement with 150 sxs cwc.
Well flowing tubing 15#. Backside 85# - shut in tubing - 100# backside.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2002 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tied onto tubing - pumped 50 sxs 60/40 pozmix - 10% gel.
Max. P.S.I. 200#. S.I.P. 0#.
Cement circulated on backside. Shut in.
Hooked up to backside - pumped 75 sxs with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.
Tied back onto tubing - pumped 100 sxs cement with 50# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

NOV 27 2002

Remarks: WELL HISTORY AND DRILLERS LOG ATTACHED. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-2-02
VAL. NO. 2003060882

NOV 25 2002

HEATHMAN-SEELIGSON

#5

WAITE

32-10-20W
SW SW NE

Contr. _____ ROOKS County

E 2179 RB Comm. _____ Comp. 1-14-55 IP 265 BOPD

Tops	Depth	Datum
ANH	1633	546
HEEB	3414	-1235
LANS	3450	-1271
B/KC	3671	-1492
CONG	3704	-1525
SIMP	3720	-1541
ARB	3739	-1560
TD	3753	-1574

Casing

8" 155

5" 3741

DST 3442-96/1 HR, 600' SLT WTR, BHP 1120#
 DST 3507-39/1 HR, 305' FL (185' WTR, 120'
 WTR & OIL), BHP 920#: DST 3564-3620/1 HR
 180' GAS, 270' FL (60' SL OCM, 60' H OCM
 60' V H OCM, 90' OIL), BHP 1010#: DST
 3662-60/1 HR, 15' MUD, BHP 0#
 DD 3746: BAIL 1/2 BOPH: DD 3753: SWB 1 1/2
 BOPH: ACID 1000: SWB 10 BOPH/3 HRS

ALLPHIN NW POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS