

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-21,535-000

NE-SE-SE, Sec. 32, T 10 S, R 20 (W) ^{AMB}

990 feet from N(S) section line ^{ICE}

330 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5938

Lease Name McKenna Well # 'D'-4

Operator: Petroleum, Inc.
Name &
Address

County Rooks

Box 1447
St. Bend, Kansas
67530

Well Total Depth 3722 feet 120.97

Conductor Pipe: Size - feet -

Surface Casing: Size 8 1/8" feet 245' circ cont.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineers License Number _____

Address St. Bend, Kansas 67530

Company to plug at: Hour: 2:00 P.M. Day: 30 Month: 12 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mr. Pulley

(company name) Rockhold Engineers (phone) _____

were: 5 1/2" csg @ 3725 P.B. w/ 5 sy cont, sanded
hole to 3670' and dumped 5 sacks cont. Shot csg
@ 3300', 3000', 2750', and 2500'. Pulled 63 joints
of 5 1/2" csg.

Ordered 190 sy 50 poz 6% gel + 3% cc, 25 sy gel, 5 sy hulls

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 P.M. Day: 30 Month: 12 Year: 1983

ACTUAL PLUGGING REPORT

Impd in 2 sy hulls 50 sy cont w/ hull, 10 sy gel,
70 sy cont w/ 1 sy hull, 15 sy gel w/ 1 hull, and 70 sy
cont. max P.S.I 300"

Shut-in " 100"

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 04 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

FORM CP-2/3
Rev. 9-82

DATE 6-5-84

INV. NO. 1819