

CONTINENTAL OIL  
ALL PHIN LEASES  
DID NOT FIND  
SCOP CARD OR  
ANY INFO IN FILE  
FOR A  
WELL AT  
THIS LOCATION  
4-042045

15-163-02228-00-02

API Number: ~~15-163-19004-0000~~

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE  
~~NE NE NW~~ /4 SEC. 33, 10 S, 20 W  
~~4950-4290~~ feet from S section line  
2970 feet from E Section line

Operator license# 5030  
Operator: Vess Oil Corporation  
Address: 8100 E. 22<sup>nd</sup> St. Bldg 300  
Wichita, Kansas 67226

329  
KCC  
12/2/99

Lease: Trico East Well # 108  
County: Rooks  
Well total depth 3691 feet  
Conductor Pipe: \_\_\_\_\_ inch @ \_\_\_\_\_ feet  
Surface Pipe: 8 5/8 Inch 250 Feet  
W/175 sxs cmt.

Aband. oil well ~~\_\_\_\_\_~~, Gas well \_\_\_\_\_, Input well X, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 3:00 P.M. Day: 29 Month: March Year: 2000

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: \_\_\_\_\_

Were: Ordered 275 sxs 60/40 pozmix - 10% gel and 700# hulls and 10 sxs gel.  
5 1/2" casing set at 3690' w/150 sxs cement. Perf at 3178' - 3500'.  
Perf. Anhy at 1608'. Dakota at 850'. T.O. Fish 3100'.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 6:00 P.M., Day 29, Month: March, Year: 2000

Actual plugging report: R.I.H. with tubing to 3100'. Spotted 50 sxs cement with 300# hulls.  
Pulled to 2900'. Spotted 10 sxs gel. Pulled to 1750' - spotted 135 sxs cement with 300#  
hulls to circulate at surface. P.O.O.H. with tubing. Squeezed casing with 45 sxs cement.  
Max. P.S.I. 300#. 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 400#.

Remarks:  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD X Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING X CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did[ X ] / did not[ ] observe the plugging.

INVOICED  
4/20/00  
06/623

RECEIVED  
STATE CORPORATION COMMISSION  
(agent)

APR 18 2000  
4-18-2000  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-2/3

005/29/01  
R