

To: 6 070741  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-13  
API NUMBER 15- 195-21,453-00-00

SE NE NW, SEC. 34, T 12 S, R 21 W/E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9346

Lease Name Seitz Barnhart Well # A-1

Operator: Glenn Q. Diehl Oil Op

County Trego 127.66

Name & Address Box 234

Well Total Depth 3928 feet

Hays, Ks. 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Glenn Diehl

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_

Address Box 31 Russell, Ks. 67665

Company to plug at: Hour: 1:00PM Day: 13 Month: Jan Year: 19 89

Plugging proposal received from Glenn Diehl

(company name) Glenn O. Diehl Oil Operations (phone) \_\_\_\_\_

were: 8 5/8" 259' S.P. cwc w/180 sks cement. 5 1/2" casing set at 3921' w/175 sks cement.

Port collar at 1658' circulated cement to surface w/NA. Perfs 3906' - 13'. No casing

recovery. Proposal 300 sks 60/40 Poz 6% Gel and 5 sks Hulls. Load both 5 1/2" and 8 5/8" annulus  
with cement and shut in under pressure.

\_\_\_\_\_ Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30PM Day: 13 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ordered 300 sks 60/40 Poz 6% Gel and 5 sks Hulls pumped

in with pump truck. 1. Pressured 5 1/2" and 8 5/8" annulus with cement. 500 psig max shut in  
at 500 psig. Did not take any cement. 2. Pumped in 5 1/2" casing 300sks cement w/5 sks Hulls added  
in. Max pressure 150 psig. Cemented by Allied Cement.

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACK of CONSERVATION DIVISION  
Wichita, Kansas)

**INVOICED**  
I (did not) observe this plugging.

DATE 1-27-89

Signed Marion J. Schmidt  
(Marion J. Schmidt)

INV. NO. 23793

RECEIVED  
STATE CORPORATION COMMISSION  
01-26-1989  
JAN 26 1989