

1-31

4-050265

20798 -00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-195-~~5064~~-00-00

SW SW SW /4 SEC. 34, 12 S, 21 W  
330 feet from S section line  
4950 feet from E section line

Operator license# 3456

Lease: Schoenthaler Well # 2

Operator: AFG Energy, Inc.

County: Trego 125.77

Address: P.O. Box 458  
Hays, Kansas 67601  
913-625-6374

Well total depth 3870 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 239 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address:

Company to plug at: Hour: A.M. Day: 31 Month: January Year: 1997

Plugging proposal received from: Terry Piesker

Company: Phone:

Were: 8 5/8" set at 239' w/175 sxs. 5 1/2" set at 3855' w/100 sxs.  
Anhydrite at 1572' - D.V. set at 1589' w/375 sxs. Perfs. 3554' - 3870'.

RECEIVED  
KANSAS CORP. COMM  
1997 FEB 12 12:12 PM  
02-12-1997

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour 11:00A.M., Day: 31, Month: January, Year: 1997

Actual plugging report: Backside full pressured to 300 P.S.I. Held. Tied onto 5 1/2" casing pumped and squeezed 280 sxs cement 60/40 pozmix - 10% gel - 500# hulls. Max. P.S.I. 1000#. S.I.P. 800#.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 2202 GL

I did [ X ] / did not [ ] observe the plugging.

Marvin Miller  
(agent)

Form CP-2/3

INVOICED

DATE FEB 13 1997

INV. NO. 47557

1-31