

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02235-00-00  
Spot: CS2S2NW Sec/Twnshp/Rge: 34-10S-20W  
330 feet from S Section Line, 1320 feet from W Section Line of NW 1/4  
Lease/Unit Name: BRIGGS Well Number: 1 <sup>PT</sup> REC  
County: ROOKS Total Vertical Depth: 3712 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 244 175 SX CMT  
Production: Size 5.5 feet: 3708 200 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

\$120.64

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2001 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/10/2001 12:15 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perf. casing at 1675' and 960'.  
5 1/2" casing - squeezed down 320 sxs 60/40 pozmix - 10% gel with 700# hulls.  
Max. P.S.I. 300#. S.I.P. 300#.  
8 5/8" S.P. - squeezed 15 sxs 60/40 pozmix - 10% gel.

RECEIVED  
AUG 15 2001  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICE

DATE 8-15-01

NO. 2002060240

Form CP-2/3

AUG 13 2001

CHESTER WILLIAMS

#1 BRIGGS

34-10-20W  
S2 S2 NW

Contr. D &amp; D DRILLING

ROOKS County


E 2128KB Comm. 3/1/63 Comp. 4/18/63 IP PMP 35 BOPD/ARB

3708-12

SMP Tops	Depth	Datum
ANH	1571	+557
TOP	3162	-1034
HEEB	3372	-1244
TOR	3395	-1267
LANS	3411	-1283
B/KC	3621	-1493
CONG	3664	-1536
SIMP	3692	-1564
ARB	3707	-1579
TD	3712	-1584

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing  
8" 244/175 SX:  
5" 3708/200 SX:  
DST 3184-3336/1 HR, GB TO FB, 200'  
M + SPEC OIL, 440' WM, BHP 1100-  
1000#/20", FP 270-320#:  
DST 3434-90/1 HR, FB TO WB, 120'  
GAS, 30' MCO, 120' OCM, BHP 750#/  
20"-690#/30"; FP 80-110#:  
DST 3515-3618/2 HRS, 240' GAS, 120'  
M FROG OIL, 450' VHO & GCM, BHP  
670-630#/30", FP 70-260#:  
DST 3704-12/2 HRS, FB, 60' MCO,  
200' FREE GASY OIL, BHP 1010-  
TRICO 970#/30", FP 10-110#:  
NO LG:



COTD: FU 1200' OIL/12  
HRS: A 500: SWB 2 1/2 BOPH  
12 HRS: POP:  
GEOL-JIM CLARK