

15-065 ~~03070~~ 03320-00-00

Form CP-3
Rev. 6-26-62

KANSAS

A
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

APR 18 1967
CONSERVATION DIVISION
WICHITA, KANSAS
4/18/67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Suite B-400, 1740 Broadway, Denver, Colorado.

Lease Name Jones Well No. 1

Location SE-SE-SW Sec. 32 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3611

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 3:00PM Day 15 Month 4 Year 1967

The Above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 175 Sx.

3611'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to 3508'. Top perforations @ 3442'.

Sanded well back to 3425' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" and squeezed well with 40 Sx. gel using 4 sacks hulls in

initial gel and followed with 75 Sx. cement. Max. pump-in pressure

750#. Final shut-in pressure 275#. (Recovered 2532' 5 1/2" casing).

(Mudding and cementing operations performed by Globe Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/18/67

INV. NO. 5069-4

Signed: *N. L. Dechals*
Well Plugging Supervisor