

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 94-11 County: Rooks
Location: NW NE NW Sec. 33 Twp. 10 Rge. 20 (E) (W)
Name of Field: _____ Total Depth: 2400 3785

I have this date completed supervision of plugging of:

Lease Name: Allphin Well No. 9

Operator's Full Name: Continental Oil Co

Complete Address: Box 98 Plainville, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: cathodic electronic pipe corrosion test

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 23 Month 5 Year 58

The above well was plugged as follows:

8 5/8" at 221' circulated with cement, 5 1/2" 2336'

Pulled 2336' 5 1/2" to 550', circulated hole with heavy mud (Gel) at

550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to

210', displaced 20 sax cement through 5 1/2" at 210', heavy mud to

35', set rock and 10 sax cement to bottom cellar.

Signed: *Edson P. [Signature]*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

6-2-1958

