

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

6-2-1958

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

File No. 94-10 County: Rooks
Location: CW $\frac{1}{2}$ W $\frac{1}{2}$ NW Sec. 33 Twp. 10 Rge. 20 (E) (W)
Name of Field: _____ Total Depth: 2400 3840

I have this date completed supervision of plugging of:

Lease Name: Allphin Well No. 3

Operator's Full Name: Continental Oil Co

Complete Address: Box 98 Plainville, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: cathodic electronic pipe corrosion test

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 21 Month 5 Year 58

The above well was plugged as follows:

8 5/8" at 263'b circulated with cement - 5 $\frac{1}{2}$ " 2336',

Pulled 2336' 5 $\frac{1}{2}$ " to 550', circulated hole with heavy mud (Gel),

displaced 20 sax cement through 5 $\frac{1}{2}$ " at 550', heavy mud to 240',

displaced 20 sax cement through 5 $\frac{1}{2}$ " at 240', heavy mud to 35', set

rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply pump truck.

Signed: *Edson L. ...*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

