

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6-29-1962
JUN 2 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Co

Complete Address: Box 98 Plainville, Kansas

Lease Name Allphin Well No. 3

Location 1320' from N line 440' from West Line Sec. 33 Twp. 10 Rge. (E) (W) 20
APPROX W 1/2 N 1/2 NW 1/4

County Rocks Total Depth original 3840 Drilled out to 2137'

Abandoned Oil Well Gas Well Input Well SWD Well D & A ✓

Other well as hereafter indicated: Experimental corrosion mud test on pipe

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 9:30AM Day 26 Month 6 Year 62

The Above well was plugged as follows:

8 5/8" 259' circulated with cement - 5 1/2" swung at 2137' mudded with test mud.

Pulled 5 1/2" to 575', circulated hole with heavy gel mud at 575' (25 sax gel), displaced 20 sax cement through 5 1/2" at 575', heavy mud to 225', displaced 20 sax cement through 5 1/2" at 225', heavy mud to 30', cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 9/3/62

INV. NO. 5509-W

Signed: Leon Lee
Well Plugging Supervisor