

CP-3

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION  
6-29-1962  
JUN 29 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Continental Oil Co  
Complete Address: Box 98 Plainville, Kansas  
Lease Name Allphin Well No. 9  
Location 330' from N line & 1650' from W line Sec. 33 Twp. 10 Rge. (E) (W) 20  
original 3785  
County Rooks Total Depth Washed out to 2028'  
Abandoned Oil Well Gas Well Input Well SWD Well D & A ✓  
Other well as hereafter indicated: Experimental corrosion mud test on pipe  
Plugging Contractor: Knight Casing Pulling  
Address: Chase, Kansas License No. 436  
Operation Completed: Hour 1PM Day 27 Month 6 Year 62

The Above well was plugged as follows:

8 5/8" 221' circulated with cement - 5 1/2" 2028' mudded.  
pulled 5 1/2" to 500', circulated hole with heavy gel mud through 5 1/2" at  
500' ( 8 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud  
to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to  
35', set bridge and filled to bottom cellar with cement.  
Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 7/3/62  
INV. NO. 5306-u

Signed: [Signature]  
Well Plugging Supervisor