

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. John Crowe of Groveny Oily Co. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Pet Inc

Complete Address: Great Bend Kan.

Lease Name: Metheny Well No. 1

Location: Sw-Nw-Ne Sec. 29 Twp. 10 Rge. 20 (E)(W)

County Rooks Total Depth 3794 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crowe was instructed to plug the well as follows:
Jett pits circulate hole with heavy mud, set cementing plug at 540 ft
and displaced 70 sac cement thru drill pipe, heavy mud to 210 ft., set
cementing plug and displace 70 sac cement, heavy mud to 40 ft., set
cementing plug, 1/2 sac hulls and 10 sac cement, cementing to base of collar.

Very truly yours,
Gilbert P. Leiker
Conservation Division Agent