

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Crowe of Grout Drilling Co. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Pet Inc

Complete Address: Great Bend, Kansas

Lease Name: McKenna Well No. B 3

Location: N 1/2 - N 1/2 - Sec Sec 32 Twp. 10 Rge. 20 (E)(W)

County Cooks Total Depth 3780 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Crowe was instructed to plug the well as follows:

~~Jet pits circulate hole with heavy mud, set cementing plug at 540 ft., and displace 20 sac cement thru drill pipe, heavy mud to 200 ft., set cementing plug, and displace 20 sac cement, heavy mud to 40 ft., set cementing plug, 1 sac balls and 1/2 sac cement, cementing to base of Celler.~~

Very truly yours,
Gilbert P. Leiker
Gilbert P. Leiker
Conservation Division Agent