


15-195-00312-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County, Sec. 29 Twp. 12 Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW/4
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Powers Well No. 1
Office Address 908 Palace Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 7, 19 55
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary mud to 214', set plug
and cemented with 15 sacks cement through drill pipe.
Mudded to 35', set plug and cemented with 10 sacks cement
to the surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg employee of Contractor
(employee of owner or owner's representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 55

My commission expires February 13, 1956. Rose Fussey Notary Public.

PLUGGING
FILE SEC 29 T 12 R 21 W
BOOK PAGE 24 LINE 8
12-23-1955
REGION

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Herman Geo. Kaiser & Francis Oil & Gas, Inc.

15-00312-00-00
 SEC. 29 T. 12S R. 21W
 LOC. SE SE SW

FARM Powers NO. 1

TOTAL DEPTH 3980'
 COMM. 11/25/55 COMP. 12/8/55
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Trego
 KANSAS



CASING
 20 10
 15 8 214'
 12 6
 13 5

ELEVATION 2249 K.B.
 PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Shale	100
Shale & Sand Streaks	150
Shale & Shells	1080
Sand	1360
Shale	1385
Shale, Shells & Red Bed	1665
Anhydrite	1705
Shale & Shells	1985
Shale, Shells & Salt	2240
Shale & Lime	3538
Lime	3573
Lime & Shale	3620
Lime	3715
Lime & Shale	3740
Lime	3790
Lime & Shale (Cherty)	3945
Lime	3946
Lime & Chert	3980

FORMATION TOPS

HEEBNER	3514
TORONTO	3535
LANSING	3548
BASE KANSAS CITY	3799
MARMATON CHERT	3876
CHERTY CONGLOMERATE	3918
SIMPSON SHALE	3930
ARBUCKLE	3940

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *P.L. Spruill*

STATE OF KANSAS }
 } SS:
 COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 13th day of December, 1955.

PLUGGING
 FILE SEC. 29 T. 12 R. 21W
 BOOK PAGE 24 LINE 8

Rose Jurey
 Notary Public

My Commission expires February 13, 1956.

PLUGGING
 FILE SEC. 29 T. 12 R. 21W
 BOOK PAGE 24 LINE 8

12-23-1955
 Notary Public
 Wichita, Kansas