

15-95-20595-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Trego County, Sec. 29 Twp. 12 Rge. 21 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C N/2 N/2 NE

Lease Owner Halliburton Oil Producing Company
Lease Name BLAKELY Well No. 1

Office Address 2915 Classen Boulevard, Oklahoma City
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Dec. 6 19 79
Application for plugging filed (verbally) Dec. 6 19 79
Application for plugging approved (verbally) Dec. 6 19 79
Plugging commenced Dec. 6 19 79
Plugging completed Dec. 6 19 79

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

T.D. 3960'

Set 1st plug at 700' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 3 sacks
mousehole with 2 sacks.

Cemented with 50/50 posmix, 6% gel.
Job was complete at 11:00 p.m., 12-06-79.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1979



My commission expires 08-21-82.

Sherrie L. Brooks Notary Public.

15-195-20595-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Halliburton Oil Producing Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Blakely #1
 LOCATION: C N/2 N/2 NE, Section 29-12-21, Trego County, Kansas
 SPUD DATE: November 28, 1979
 COMPLETION DATE: December 06, 1979

0	710	Sand and shale
710	1157	Shale and sand
1157	1375	Sand
1357	1653	Shale
1653	1701	Anhydrite
1701	3030	Shale
3030	3131	Shale and lime
3131	3404	Lime
3404	3515	Shale and lime
3515	3960	Lime
	3960	Rotary Total Depth

Spud hole at 11:30 a.m., November 28, 1979. Drilled 260' of 12 1/4" hole. Ran 6 joints of 8-5/8" used 24# casing. (Talley 251.28') Set at 257' KB with 130 sacks of common cement, 3% Ca.Cl., 2% gel. Pumped plug to 240' KB. Cement did circulate. Plug was down at 7:15 p.m., November 28, 1979.

T.D. 3960'. Set 1st plug at 700' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 3 sacks and mousehole with 2 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 11:00 p.m., December 06, 1979.

SAMPLE TOPS:

Anhydrite 1653'
 B/Anhydrite 1701'

RECEIVED
 STATE COMMISSION
 DEC 11 1979
 12-11-1979
 COMMISSION PUBLIC

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Blakely #1, C N/2 N/2 NE, Section 29-12-21, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 10th day of December, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.