


15-195-01433-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Trego County, Sec. 33 Twp. 12 Rge. 21 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines SW SE SW  
Lease Owner PETROLEUM, INC.  
Lease Name Merrill Well No. 1  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 6 19 55  
Application for plugging filed May 13 19 57  
Application for plugging approved May 15 19 57  
Plugging commenced July 6 19 57  
Plugging completed July 9 19 57  
Reason for abandonment of well or producing formation Depletion of  
producing zones.  
If a producing well is abandoned, date of last production December 31 19 56  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation Arbuckle Depth to top 3882' Bottom --- Total Depth of Well 3889 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Arbuckle</u>	<u>Water and</u>			<u>8 5/8"</u>	<u>200'</u>	<u>None</u>
	<u>little oil</u>	<u>3884'</u>	<u>3889'</u>	<u>5 1/2"</u>	<u>3884'</u>	<u>2400'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with crushed rock from 3889' to 3870' and placed 4 sacks cement on top of rock. Mudded up with heavy mud to 608'. Cemented from 608' to base of well cellar with 100 sacks cement, 25 sacks strata-crete, 6% gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service  
Address 102 West 18th Street Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Don Searle (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July 19 57

My commission expires July 11, 1960

[Signature]  
Notary Public.

STAT. CORP. COM. IN COMMISSION  
07-16-1957  
JUL 16 1957

PLUGGING  
FILE SEC 33 T 12 R 21 W  
BOOK PAGE 12 LINE 39

CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

COMPANY **Petroleum, Inc.**

15-195-01433<sup>0000</sup> SEC. 33 T. 12 R. 21W

FARM **MERRILL**

NO. **1**

LOC. **SW SE SW**


TOTAL DEPTH **3888'**

COUNTY **Trego County, Kansas**

COMM. **March 14, 1955**

COMP. **March 29, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 202' w/200 sax.  
5 1/2" @ 3884' w/80 sax.**

ELEVATION **2215 RB**

PRODUCTION **Arbuckle**

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Clay & Sand
1618	Shale & Sand
1648	Anhydrite
2350	Shale & Shells
2540	Lime & Shale
2575	Shale & Shells
2680	Lime & Shale
2885	Shale & Shells
3215	Lime & Shale
3290	Lime
3445	Lime & Shale
3888	Lime

Tops:

Toronto:	3495 (-1280)
Lansing:	3508 (-1293)
Conglomerate:	3870 (-1655)
Arbuckle:	3882 (-1667)

R.T.D. 3888

State of KANSAS  
County of SEDGWICK

**PLUGGING**  
FILE SEC. 33 T. 12 R. 21W  
BOOK PAGE 12 LINE 39

STAMPED  
JUL 10 1955  
07-16-1955  
CON. SECTION

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the MERRILL #1 well.

Karl E. Becker

Subscribed and sworn to before me this 12th day of April, 1955

My Commission Expires: 8-11-58

Peter M. Edwards  
NOTARY PUBLIC